

EXHIBIT J

McDowell Point, Naperville IL				
SITE METRIC / UNIT TABULATION				2/26/18
UNIT NAME	UNIT TYPE	RENTABLE AREA (NET)	UNIT COUNT	OVERALL UNIT MIX
A1A	1BR/1BA	758	45	
A2	1BR+DEN/1BA	938	36	
A3	1BR+DEN/1BA	1031	6	
A4	1BR/1BA	968	3	51.7%
B1	2BR/2BA	1050	34	
B1A	2BR/2BA	1146	18	
B2	2BR/2BA	1282	14	
B3	2BR/2BA	1245	4	40.2%
C1	3BR/3BA	1496	4	
C2	3BR/3BA	1365	3	
C3	3BR/3BA	1818	3	
C4	3BR/3BA	1680	4	8.0%
TOTALS			174	100.0%
SITE ACREAGE:		8.26 ACRES		
DENSITY:		21.07 UNITS/ACRE		
PARKING:		1.75 PARKING SPACES/UNIT		
PROVIDED	233 GARAGE SPACES	71 SURFACE SPACES		



CURRENT FLOOR AREA RATIO: 0.7 (MAX. REQUIRED: 1.5)
 TOTAL FLOOR AREA: 251,863 S.F.
 (NOT INCLUDING 84,439 S.F. GARAGE AREA)
 CURRENT OPEN SPACE: 71.1% (255,654 S.F.)
 (MIN. REQUIRED: 35%)

DEFINITIONS

FLOOR AREA RATIO: THE NUMERICAL VALUE OBTAINED BY DIVIDING THE FLOOR AREA WITHIN A BUILDING OR STRUCTURE ON A LOT BY THE AREA OF SUCH LOT, THE FLOOR AREA RATIO, AS SPECIFIED FOR EACH ZONING DISTRICT, WHEN MULTIPLIED BY THE AREA OF THE LOT IN SQUARE FEET, SHALL DETERMINE THE MAXIMUM PERMISSIBLE FLOOR AREA FOR THE BUILDING OR STRUCTURE ON THE LOT.

OPEN SPACE: THAT PORTION OF A LOT OR PARCEL OF LAND UNOCCUPIED BY BUILDINGS, STRUCTURES, RIGHTS-OF-WAY AND OFF STREET PARKING, OR LOADING FACILITIES.

 OPEN SPACE AREA



© 2018 by HUMPHREYS & PARTNERS ARCHITECTS, L.P. The arrangements depicted herein are the sole property of Humphreys & Partners Architects, L.P. and may not be reproduced in any form without its written permission. Architectural conceptual site plans are for feasibility purpose only. Reviewers may incur due to further investigation from regulatory authorities and building code analysis. Dimensions shown are of a strategic intent only. Refer to site plan and civil drawings for technical information and measurements.