

Proposal

MUSTANG CONSTRUCTION, INC.

1805 High Grove Lane
Naperville, Illinois 60540
(630) 355-8094
FAX (630) 305-6596

| | | |
|--|--|--------------------------------|
| PROPOSAL SUBMITTED TO: TURNING POINTE, AUTISM FOUNDATION ATTN: BARBARA BRAUER | PHONE 630-615-6033 | DATE October 1, 2020 |
| STREET 1500 W. OGDEN AVENUE | JOB NAME: HVAC REPLACEMENT | |
| CITY, STATE, and ZIP CODE NAPERVILLE, ILLINOIS 60540 | JOB LOCATION: 1500 W. OGDEN AVENUE, NAPERVILLE, IL 60540 | |

We propose hereby to furnish material and labor- complete in accordance with specifications below

| |
|------------------------------------|
| Payment to be made as follows: |
| UPON INVOICING & COMPLETION OF JOB |

All material is guaranteed to be as specified. All work to be completed in a workmanlike manner according to standard practices. Any alteration or deviation from specifications below involving extra costs will be executed only upon written orders, and will become an extra charge over and above the estimate. All agreements contingent upon strikes, accidents or delays beyond our control. Owner to carry fire, tornado and other necessary insurance. Our workers are fully covered by Workman’s Compensation Insurance.

AUTHORIZED SIGNATURE: *R. G. Ripper*
R.G.RIPPER, VICE. PRESIDENT

Note: This proposal may be withdrawn by us if not accepted within 30 days.

We hereby submit specifications and estimates for the following labor and materials:

Install two RTU’s & Removal of old (2) RTU’s

RTU #1

- Install a Trane TSD240F4ROC 20 Ton Cooling only RTU.
- Unit to include; Dx cooling Stand efficiency, downflow, reliatel, low leak economizer, vav (dtc) with supply VFD w/ bypass, BACnet communications interface, and programmable zone sensor.

RTU #2

- Install a Trane TSD300F4ROC 25 Ton Cooling only RTU
- Unit to include; Dx cooling Stand efficiency, downflow, reliatel, low leak economizer, vav (dtc) with supply VFD w/ bypass, BACnet communications interface, and programmable zone sensor.
- Work to include removal and haul away of all existing equipment. Crane Fee up to 90T (Minimum 8 hours), labor to install, and supervision.

Total: \$56,730.92

We did not include the integration, programing, and installation of controls for existing building automation system. This would be part of what your building engineering company does if it is existing. It is unknown if you currently have.

Not Included:

- Permits, Fees, Architectural Drawings, City inspections, Electrical, prevailing wage, painting, staining, masonry, plumbing, carpentry, air balancing, penetrations through masonry, steel, or wood structures,
- Overtime, weekend work, after hours work.
- Roof Screening

Acceptance of Proposal- The above prices, specifications and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified. Payment will be made as outlined above.

SIGNATURE: _____

SIGNATURE: _____

DATE OF ACCEPTANCE: _____

p:\mustang\proposals-mustang\mustangmisc\TurningpointeHVACReplacement.doc