WEST BRANCH Dupage RIVER STABILIZATION NAPERVILLE PARK DISTRICT

INDEX TO DRAWINGS

COVER

QUANTITIES, LEGEND

EXISTING CONDITIONS/DEMOLITION PLAN


PROPOSED IMPROVEMENTS PLAN

CROSS SECTIONS

12.-13. SWPPP

SWPPP NOTES SWPPP DETAILS 16.-18. PLANTING PLAN PLANTING DETAILS

STABILIZATION DETAILS



LOCATION MAP

PREPARED FOR: NAPERVILLE PARK DISTRICT 320 W. JACKSON AVENUE NAPERVILLE, ILLINOIS 60540

SITE BENCHMARK = DPC38091302

ELEV. 693.009

BENCHMARK CP #1

BENCHMARK CP #4

ELEV. 673.49 (NAVD 88)


ELEV. 672.11 (NAVD 88)

1905-693 (ALSO NAPERVILLE DATUM NA13003).

SET MAG NAIL IN PATH STA. 115+88.34, 7.45'LT.

SET IRON PIPE STA. 104+40.67, 4.62'RT.

PHONE: (630) 848-5012 FAX: (630) 848-5019



FULL SIZE PLANS HAVE BEEN PREPARED USING STANDARD ENGINEERING SCALES. REDUCED SIZED PLANS WILL NOT CONFORM TO STANDARD SCALES. IN MAKING MEASUREMENTS ON REDUCED PLANS, THE ABOVE SCALES MAY BE USED.



CHAMPAIGN, ILLINOIS 61821 PHONE (217) 351-6268 FAX (217) 355-1902

3S701 WEST AVENUE, SUITE 150 WARRENVILLE, ILLINOIS 60555 PHONE (630) 393-3060 FAX (630) 393-2152

10 S. RIVERSIDE PLAZA, SUITE 875 CHICAGO, ILLINOIS 60606 PHONE (312) 474-7841 FAX (312) 474-6099

ALUM TABLET SET VERT. IN WALL OF NICHOLS LIBRARY. A GEOLOG DISK READS

Marty J. Michalisko, P.E. IL. P.E. NO. 062-058762 Expires: November 30, 2025


50% SUBMITTAL: NOVEMBER 10, 2023 ORIGINAL SUBMITTAL: SEPTEMBER, 2023

ERA JOB NO.: W23198

2416 GALEN DRIVE

REVISED: JUNE 26, 2024

SUMMARY OF QUANTITIES



STAGING DIAGRAM SCALE 1":120"

REVISIONS: DRAWN BY: DATE BY DESCRIPTION DESCRIPTION DATE BY APPROVED BY: MM



PHONE (312) 474-7841 FAX (312) 474-6099

2416 GALEN DRIVE CHAMPAIGN, ILLINOIS 61821 PHONE (217) 351-6268 FAX (217) 355-1902

WEST BRANCH DuPAGE RIVER STABILIZATION NAPERVILLE PARK DISTRICT

SUMMARY OF QUANTITIES, LEGEND

SIDEWALK REMOVE & REPLACE

TREE(CONIFEROUS)

LANDSCAPED AREA

BUTT JOINT

SCALE: N.T.S. *DATE:* July, 2024 *JOB NO:* W23198 SHEET_2_OF_

TELEPHONE WATER OVERHEAD WIRE MANHOLE \bigcirc CATCH BASIN FLARED END SECTION (FES) **⊠** F FILL STRUCTURE $\bigcirc \mathbb{R}$ REMOVE STRUCTURE RECONSTRUCT STRUCTURE ADJUST STRUCTURE VALVE VAULT VALVE & BOX BUFFALO BOX HYDRANT GAS VALVE HANDHOLE UTILITY PEDESTAL UTILITY POLE UTILITY POLE W/STREET LIGHT STREET LIGHT WALKWAY LIGHT YARD LIGHT SPOT LIGHT STREET LIGHT CONTROLLER BASKETBALL HOOP MAIL BOX INLET FILTER FENCE WOOD FENCE REMOVE TREE TREE(DECIDUOUS)

LEGEND

<u>PROPOSED</u>

<u>EXISTING</u>

=======

CURB & GUTTER

BARRIER CURB


EDGE OF PAVEMENT


10 YR FLOOD PLAIN 100 YR FLOOD PLAIN


ELECTRIC


AT&T


SANITARY SEWER STORM SEWER DRAIN TILE UNDERDRAIN FLOODWAY























3S701 WEST AVENUE, SUITE 150
WARRENVILLE, ILLINOIS 60555
PHONE (630) 393-3060

10 S. RIVERSIDE PLAZA , SUITE 875
CHICAGO, ILLINOIS 60606
PHONE (312) 474-7841

FAX (312) 474-6099

ENGINEERING
RESOURCE ASSOCIATES

3S701 WEST AVENUE, S
WARRENVILLE, ILLINOIS 6
PHONE (630) 393-3060
FAX (630) 393-2152

2416 GALEN DRIVE CHAMPAIGN, ILLINOIS 61821

PHONE (217) 351-6268

FAX (217) 355-1902

STABILIZATION

NAPERVILLE PARK DISTRICT

DRAWN BY:

APPROVED BY:

DESCRIPTION

DATE BY

DESCRIPTION

DATE BY

SCALE:1"=10'H;1"=5'V DATE: July, 2024

JOB NO: W23198 CROSS SECTIONS STA. 111+34 TO STA. 116+19 SHEET_ 11_OF___

<u>LEGEND</u>


PROP ROCK TOE


— — — EXISTING SURFACE

— — WETLAND BOUNDARY

PROPOSED SURFACE

PROP LIMESTONE OUTCROPPING





STORM WATER POLLUTION PREVENTION PLAN

THE FOLLOWING PLAN IS ESTABLISHED AND INCORPORATED IN THE PROJECT TO DIRECT THE CONTRACTOR IN THE PLACEMENT OF TEMPORARY EROSION AND SEDIMENT CONTROL SYSTEMS AND TO PROVIDE A STORM WATER POLLUTION PREVENTION PLAN FOR COMPLIANCE UNDER NPDES.

THE PURPOSE OF THIS PLAN IS TO MINIMIZE EROSION WITHIN THE CONSTRUCTION SITE AND TO LIMIT SEDIMENT FROM LEAVING THE CONSTRUCTION SITE BY UTILIZING PROPER TEMPORARY EROSION AND SEDIMENT CONTROL SYSTEMS AND PROVIDING GROUND COVER WITHIN A REASONABLE AMOUNT OF TIME.

CERTAIN SEDIMENT CONTROL FACILITIES SHALL BE INSTALLED BY THE CONTRACTOR AT THE BEGINNING OF CONSTRUCTION. OTHER ITEMS SHALL BE INSTALLED BY THE CONTRACTOR AS DIRECTED BY THE ENGINEER ON A CASE BY CASE SITUATION DEPENDING ON THE CONTRACTOR'S SEQUENCE OF ACTIVITIES, TIME OF YEAR, AND EXPECTED WEATHER CONDITIONS.

THE CONTRACTOR SHALL INSTALL PERMANENT EROSION CONTROL SYSTEMS AND SEEDING WITHIN A TIME FRAME SPECIFIED HEREIN AND AS DIRECTED BY THE ENGINEER, THEREFORE MINIMIZING THE AMOUNT OF AREA SUSCEPTIBLE TO EROSION AND REDUCING THE AMOUNT OF TEMPORARY SEEDING. THE ENGINEER WILL DETERMINE IF ANY TEMPORARY EROSION CONTROL SYSTEMS SHOWN IN THE PLAN CAN BE DELETED AND IF ANY ADDITIONAL TEMPORARY EROSION CONTROL SYSTEMS. WHICH ARE NOT INCLUDED IN THIS PLAN. SHALL BE ADDED. THE CONTRACTOR SHALL PERFORM ALL WORK AS DIRECTED BY THE ENGINEER AND AS SHOWN IN IDOT STANDARD 280001

SECTION 280. TEMPORARY EROSION CONTROL, OF THE STANDARD SPECIFICATIONS ADDITIONALLY SUPPLEMENTS THIS PLAN.

SITE DESCRIPTION. DESCRIPTION OF CONSTRUCTION ACTIVITY:

- 1. THE PROJECT IS LOCATED IN RIVERVIEW PARK, NAPERVILLE IL. ON THE WEST BRANCH DUPAGE RIVER
- 2. THE WEST BRANCH DUPAGE RIVER STABILIZATION PROJECT SHALL GENERALLY CONSIST OF THE FOLLOWING:
- INSTALLATION OF STREAMBANK STABILIZATION, STREAM BARBS, WETLAND MITIGATION AND NATURAL AREA RESTORATION, AND ASSOCIATED EROSION CONTROL MEASURES, INCLUDING IN—STREAM CONTROL MEASURES;
- TREE/BRUSH CLEARING, PLUG PLANTING, AND RESTORATION SEEDING;
- THE PROJECT ALSO INCLUDES 3 YEARS OF ECOLOGICAL MANAGEMENT, WETLAND MONITORING AND 3.) REPORTING.
- ALL OTHER COLLATERAL WORK SUCH AS RESTORATION.

DESCRIPTION OF INTENDED SEQUENCE FOR MAJOR CONSTRUCTION ACTIVITIES WHICH WILL DISTURB SOILS FOR MAJOR PORTION OF THE CONSTRUCTION SITE:

- INSTALL COFFER DAM AND SILT SCREEN.
- INSTALL ROCK TOE, STREAM BARBS, STONE OUTCROPPINGS AND RE-GRADE BANK. SITE SHALL BE TEMPORARILY STABILIZED IMMEDIATELY FOLLOWING MASS GRADING COMPLETION.
- FINE GRADING SHALL BE PERFORMED THE SITE SHALL BE SEEDED AND STABILIZED WITH BIODEGRADABLE EROSION CONTROL MAT UPON
- COMPLETION OF THE PROJECT.
- 6. TEMPORARY EROSION CONTROL MEASURES WILL BE REMOVED FOLLOWING FINAL STABILIZATION.

AREA OF CONSTRUCTION SITE:

THE TOTAL AREA OF THE CONSTRUCTION SITE IS ESTIMATED TO BE 1.61 ACRES BY WHICH 1.61 ACRES WILL BE DISTURBED BY EXCAVATION, GRADING, AND OTHER ACTIVITIES.

OTHER REPORTS. STUDIES AND PLANS. WHICH AID IN THE DEVELOPMENT OF THE STORM WATER POLLUTION PREVENTION PLAN AS REFERENCED DOCUMENTS:

- 1. INFORMATION OF THE SOILS AND TERRAIN WITHIN THE SITE WAS OBTAINED FROM TOPOGRAPHIC SURVEYS AND SOIL BORINGS THAT WERE UTILITIES FOR THE DEVELOPMENT OF THE PROPOSED TEMPORARY EROSION AND SEDIMENT CONTROL SYSTEMS.
- 2. PROJECT PLAN DOCUMENTS, SPECIFICATIONS AND SPECIAL PROVISIONS. AND PLAN DRAWINGS INDICATING DRAINAGE PATTERNS AND APPROXIMATE SLOPES ANTICIPATED AFTER GRADING ACTIVITIES WERE UTILIZED FOR THE PROPOSED PLACEMENT OF THE TEMPORARY EROSION CONTROL SYSTEMS.

DRAINAGE TRIBUTARIES AND SENSITIVE AREAS RECEIVING RUNOFF FROM THIS CONSTRUCTION SITE:

1. THE SITE DRAINS INTO WEST BRANCH DUPAGE RIVER.

THIS PLAN HAS BEEN PREPARED TO COMPLY WITH THE PROVISIONS OF THE NPDES PERMIT NUMBER ILR10 ISSUED BY THE ILLINOIS ENVIRONMENTAL PROTECTION AGENCY FOR STORM WATER DISCHARGES FROM CONSTRUCTION SITE ACTIVITIES.

I CERTIFY UNDER PENALTY OF LAW THAT THIS DOCUMENT AND ALL ATTACHMENTS WERE PREPARED UNDER MY DIRECTION OR SUPERVISION IN ACCORDANCE WITH A SYSTEM DESIGNED TO ASSURE THAT QUALIFIED PERSONNEL PROPERLY GATHERED AND EVALUATED THE INFORMATION SUBMITTED. BASED ON MY INQUIRY OF THE PERSON OR PERSONS WHO MANAGE THE SYSTEM, OR THOSE PERSONS DIRECTLY RESPONSIBLE FOR GATHERING THE INFORMATION, THE INFORMATION SUBMITTED IS TO THE BEST OF MY KNOWLEDGE AND BELIEF, TRUE, ACCURATE AND COMPLETE. I AM AWARE THAT THERE ARE SIGNIFICANT PENALTIES FOR SUBMITTING FALSE INFORMATION, INCLUDING THE POSSIBILITY OF FINE AND IMPRISONMENT FOR KNOWING VIOLATIONS.

CONTRACTOR'S CERTIFICATION

I CERTIFY UNDER PENALTY OF LAW THAT I UNDERSTAND THE TERMS AND CONDITIONS OF THE GENERAL NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES) PERMIT (ILR 10) THAT AUTHORIZES THE STORMWATER DISCHARGES ASSOCIATED WITH ACTIVITY FROM THE CONSTRUCTION SITE IDENTIFIED AS PART OF THIS CERTIFICATION.

GENERAL CONTRACTOR

SIGNATURE

COMPANY

REVISIONS:

DATE BY

SIGNATURE COMPANY

OWNER'S CERTIFICATION

"I CERTIFY UNDER PENALTY OF LAW THAT THIS DOCUMENT OR SUPERVISION IN ACCORDANCE WITH A SYSTEM DESIGNED INQUIRY OF THE PERSON OR PERSONS WHO MANAGE THE SYSTEM, OR THOSE PERSONS DIRECTLY RESPONSIBLE FOR TO THE BEST OF MY KNOWLEDGE AND BELIEF, TRUE, ACCURATE AND COMPLETE. I AM AWARE THERE ARE INCLUDING THE POSSIBILITY OF FINE AND IMPRISONMENT FOR KNOWING VIOLATIONS." <u>OWNER</u>

SEDIMENT EROSION CONTROL AND POLLUTION PREVENTION NOTES:

- 1. DURING CONSTRUCTION, AREAS OUTSIDE THE CONSTRUCTION LIMITS SHALL BE PROTECTED.
- THE CONTRACTOR SHALL NOT USE THIS AREA FOR STAGING, PARKING OF VEHICLES OF CONSTRUCTION EQUIPMENT, STORAGE OF MATERIALS OR OTHER CONSTRUCTION RELATED ACTIVITIES.
- CONSTRUCTION EQUIPMENT SHALL BE STORED AND FUELED ONLY AT DESIGNATED LOCATIONS. ALL NECESSARY MEASURES SHALL BE TAKEN TO CONTAIN ANY FUEL OR OTHER POLLUTANT IN ACCORDANCE WITH EPA WATER QUALITY REGULATIONS. LEAKING EQUIPMENT OR SUPPLIES SHALL BE IMMEDIATELY REPAIRED OR REMOVED FROM THE SITE.
- TEMPORARY SEDIMENT CONTROL SYSTEMS SHALL BE LEFT IN PLACE WITH PROPER MAINTENANCE UNTIL PERMANENT EROSION CONTROL IS IN PLACE AND WORKING PROPERLY AND ALL PERMANENT VEGETATION IS GROWING AND THRIVING.
- EROSION CONTROL MEASURES SHALL BE INSTALLED PRIOR TO START OF CONSTRUCTION ALL EROSION CONTROL MEASURES MUST BE INSPECTED WEEKLY AND AFTER EACH 1/2" RAIN EVENT
- 6. THE EROSION CONTROL BLANKET AND/OR STRAW MULCH WITH NETTING (DEPENDING ON SLOPE, SLOPE LENGTH AND FLOW RATES) SHALL BE INSTALLED ON ALL SLOPES AND IN CRITICAL AREAS (I.E. POND PERIMETER, BERMS, ETC.) IMMEDIATELY UPON FINAL GRADING
- IN AREAS WHERE WORK IS COMPLETE, PERMANENT STABILIZATION SHALL OCCUR WITHIN 7 DAYS OF COMPLETION, AND IN AREAS WHERE WORK HAS TEMPORARILY CEASED FOR 14 DAYS OR MORE, TEMPORARY STABILIZATION SHALL OCCUR BY THE 7TH DAY AFTER WORK HAS CEASED
- WINTER SHUTDOWN SHALL BE ADDRESSED EARLY IN THE FALL GROWING SEASON SO THAT SLOPES AND OTHER BARE EARTH AREAS MAY BE STABILIZED WITH TEMPORARY AND/OR PERMANENT VEGETATIVE COVER FOR PROPER EROSION AND SEDIMENT CONTROL'
- 9. ALL ADJACENT STREETS MUST BE KEPT CLEAR OF DEBRIS, INSPECTED DAILY AND CLEANED WHEN NECESSARY AND AS DIRECTED BY ENGINEER
- 10. UNLESS OTHERWISE INDICATED, ALL VEGETATIVE AND STRUCTURAL EROSION AND SEDIMENT CONTROL PRACTICES WILL BE CONSTRUCTED ACCORDING TO MINIMUM STANDARDS AND SPECIFICATIONS IN THE MOST RECENT ILLINOIS URBAN MANUAL. 11. THE KANE-DUPAGE SOIL AND WATER CONSERVATION DISTRICT (KDSWCD) MUST BE NOTIFIED ONE WEEK PRIOR TO THE PRE-CONSTRUCTION CONFERENCE, ONE WEEK PRIOR TO THE COMMENCEMENT OF LAND DISTURBING ACTIVITIES, AND ONE WEEK
- PRIOR TO THE FINAL INSPECTION. 12. A COPY OF THE APPROVED EROSION AND SEDIMENT CONTROL PLAN SHALL BE MAINTAINED ON THE SITE AT ALL TIMES. 13. PRIOR TO COMMENCING LAND-DISTURBING ACTIVITIES IN AREAS OTHER THAN INDICATED ON THESE PLANS (INCLUDING BUT
- NOT LIMITED TO, ADDITIONAL PHASES OF DEVELOPMENT AND OFF-SITE BORROW OR WASTE AREAS) A SUPPLEMENTARY EROSION CONTROL PLAN SHALL BE SUBMITTED TO THE OWNER FOR REVIEW BY THE KDSWCD. 14. THE CONTRACTOR IS RESPONSIBLE FOR INSTALLATION OF ANY ADDITIONAL EROSION CONTROL MEASURES NECESSARY TO
- PREVENT EROSION AND SEDIMENTATION AS DETERMINED BY THE KDSWCD. 15. NO WORK SHALL BE PERFORMED IN FLOWING WATER. WORK IN AND NEAR THE CRITICAL AREAS SHOULD BE ISOLATED FROM CONCENTRATED FLOWS OR STREAM FLOW. ONCE WORK IN THIS AREA BEGINS, PRIORITY SHALL BE GIVEN TO THE COMPLETION
- OF THE WORK AND FINAL STABILIZATION OF ALL DISTURBED AREAS. 16. DURING DEWATERING OPERATIONS, WATER WILL BE PUMPED INTO SEDIMENT BASINS OR SILT TRAPS. DEWATERING SEDIMENT LADEN WATER DIRECTLY INTO STREAMS, WETLANDS, FIELD TILES, OR STORMWATER STRUCTURES IS PROHIBITED.
- T IS THE RESPONSIBILITY OF THE LANDOWNER AND/OR GENERAL CONTRACTOR TO INFORM ANY SUB-CONTRACTOR(S) WHO MAY PERFORM WORK ON THIS PROJECT, OF THE REQUIREMENTS IN IMPLEMENTING AND MAINTAINING THESE EROSION CONTROL PLANS AND ASSURE COMPLIANCE WITH ALL APPLICABLE LOCAL, STATE AND FEDERAL REGULATIONS.
- 18. 14. WHERE THERE IS LOW, INTERMITTENT AMOUNTS OF DEWATERING, PUMPS WITH FILTRATION BAGS SHALL BE USED FILTRATION BAGS SHALL BE ATTACHED TO PUMP DISCHARGES AND SURROUNDED WITH A SECONDARY CONTAINMENT OR ON A STABILIZED AREA. FILTER BAGS SHALL NOT BE PLACED, WHOLE OR PARTIALLY, WITHIN AQUATIC AREAS (WETLANDS, STREAMS, ETC.) THE MATERIAL FOR THE FILTRATION BAG SHALL MEET THE REQUIREMENTS OF MATERIAL SPECIFICATION 592 GEOTEXTILE OF THE ILLINOIS URBAN MANUAL, TABLE 2, CLASS I WITH A MINIMUM TENSILE STRENGTH OF 200 LBS. THE FILTRATION BAG
- SHALL BE SIZED PER MANUFACTURER RECOMMENDATIONS AND BASED ON THE SIZE OF THE PUMP. 19. EXCAVATED AREAS SHALL BE PERMANENTLY SEEDED IMMEDIATELY AFTER FINAL GRADING. IF NOT, THEY SHALL BE
- TEMPORARILY SEEDED IF NO CONSTRUCTION ACTIVITY IN THE AREA IS PLANNED FOR SEVEN (7) DAYS. 20. TEMPORARY EROSION CONTROL SEEDING SHALL BE APPLIED AT A RATE OF 50 LBS/ACRES.
- 21. CONSTRUCTION IS COMPLETE AFTER ACCEPTANCE BY THE OWNER. MAINTENANCE UP TO THIS DATE WILL BE BY THE CONTRACTOR
- 22. NO STOCKPILING IS PERMITTED WITHIN THE FLOODPLAIN LIMITS. STOCKPILES THAT ARE TO REMAIN IN PLACE MORE THAN THREE DAYS SHALL BE PROVIDED WITH SOIL EROSION AND SEDIMENT CONTROL MEASURES.
- 23. SEDIMENT COLLECTED DURING CONSTRUCTION BY THE VARIOUS TEMPORARY SEDIMENT CONTROL SYSTEMS SHALL BE DISPOSED OF ON THE SITE ON A REGULAR BASIS, AS DIRECTED BY THE ENGINEER. THE COST OF THIS MAINTENANCE SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE PER CUBIC YARD FOR EARTH EXCAVATION.
- 24. ALL DROP INLETS ON AND ADJACENT TO THE SITE MUST HAVE A SEDIMENT TRAPPING OR CONTAINMENT DEVICE INSTALLED DURING CONSTRUCTION ACTIVITIES. FILTER FABRIC ON ITS OWN IS NOT AN APPROVED METHOD. A MANUFACTURE'S SPEC SHOULD BE USED FOR PREFABRICATED DROP INLET PROTECTION AND SHOULD BE AS THE ILLINOIS URBAN MANUAL STANDARD 861 FOR INLET PROTECTION.
- 25. ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES SHALL BE REMOVED WITHIN 30 DAYS AFTER FINAL STABILIZATION IS ACHIEVED. TRAPPED SEDIMENT AND OTHER DISTURBED SOILS RESULTING FROM TEMPORARY MEASURES SHALL
- BE PROPERLY DISPOSED OF PRIOR TO PERMANENT STABILIZATION. 26. ALL EROSION AND SEDIMENT CONTROL PRODUCTS FURNISHED SHALL BE SPECIFICALLY RECOMMENDED BY THE MANUFACTURER FOR THE USE SPECIFIED IN THE EROSION AND SEDIMENT CONTROL PLAN. PRIOR TO THE APPROVAL AND USE OF THE THE CONTRACTOR SHALL SUBMIT TO THE ENGINEER A NOTARIZED CERTIFICATION BY THE PRODUCER STATING THE INTENDED USE OF THE PRODUCT AND THAT THE PHYSICAL PROPERTIES REQUIRED FOR THIS APPLICATION ARE MET OR EXCEEDED. THE CONTRACTOR SHALL PROVIDE MANUFACTURER INSTALLATION PROCEDURES TO FACILITATE THE ENGINEER IN
- CONSTRUCTION INSPECTION. 27. THE DRAWINGS, SPECIFICATIONS AND SPECIAL PROVISIONS WILL ENSURE THAT EXISTING VEGETATION IS PRESERVED WHERE ATTAINABLE AND DISTURBED PORTIONS OF THE SITE WILL BE STABILIZED. STABILIZATION PRACTICES INCLUDE TEMPORARY SEEDING, PERMANENT SEEDING, MULCHING, PROTECTION OF TREES, PRESERVATION OF NATURAL VEGETATION, AND OTHER APPROPRIATE MEASURES AS DIRECTED BY THE ENGINEER, STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS PRACTICABLE IN PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED. BUT IN NO CASE MORE THAN 7 DAYS AFTER THE CONSTRUCTION ACTIVITY IN THAT PORTION OF THE SITE HAS TEMPORARILY OR PERMANENTLY CEASED.
- a. AREAS OF EXISTING VEGETATION, WOOD AND GRASSLANDS, OUTSIDE THE PROPOSED CONSTRUCTION LIMITS SHALL BE IDENTIFIED BY THE ENGINEER FOR PRESERVING AND SHALL BE PROTECTED FROM CONSTRUCTION ACTIVITIES.
- b. DEAD, DISEASED, OR UNSUITABLE VEGETATION WITHIN THE SITE SHALL BE REMOVED AS DIRECTED BY THE ENGINEER, ALONG
- c. BARE AND SPARSELY VEGETATED GROUND IN HIGH ERODIBLE AREAS AS DETERMINED BY THE ENGINEER SHALL BE TEMPORARILY SEEDED AT THE BEGINNING OF CONSTRUCTION WHERE NO CONSTRUCTION ACTIVITIES ARE EXPECTED WITHIN
- d. IMMEDIATELY AFTER TREE REMOVAL IS COMPLETED, AREAS WHICH ARE HIGHLY ERODIBLE AS DETERMINED BY THE ENGINEER. SHALL BE TEMPORARILY SEEDED WHEN NO CONSTRUCTION ACTIVITIES ARE EXPECTED WITHIN SEVEN (7) DAYS.
- 28. ESTABLISHMENT OR THESE TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES WILL HAVE ADDITIONAL BENIFITS TO THE PROJECT. DESIRED GRASS SEED WILL BECOME ESTABLISHED IN THESE AREAS AND WILL SPREAD SEEDS ONTO THE CONSTRUCTION SITE UNTIL PERMANENT SEEDING/MOWING AND OVER SEEDING CAN BE COMPLETED 29. THE CONTRACTOR SHALL INSTALL A DEWATERING/FILTRATION OPERATION ONCE WORK COMMENCES. THE DEWATERING
- OPERATION SHOULD INCLUDE STABILIZED INTAKE/OUTLET LOCATIONS, APPROVED FILTRATION DEVICE, AND VELOCITY DISSIPATION AT THE OUTLET. THE EXACT METHODS SHOULD BE SUBMITTED TO KDSWCD FOR REVIEW WITHIN ONE WEEK BEFORE THE IN-STREAM WORK IS PLANNED TO BEGIN. 30. THE IN-STREAM WORK SHALL BE COMPLETED AND THE ENTIRE SYSTEM, INCLUDING SIDE SLOPES, OF WEST BRANCH DUPAGE
- RIVER RESTORED AND STABILIZED BEFORE THE COFFERDAMS ARE REMOVED. 31. ALL ADJACENT STREETS MUST BE KEPT CLEAR OF DEBRIS. STREETS MUST BE INSPECTED DAILY AND CLEANED WHEN
- 32. PRIORITY SHALL BE GIVEN TO THE COMPLETION AND STABILIZATION OF THE POND AREAS. WORK IN THESE AREAS SHALL NOT BE PROLONGED IN ATTEMPT THAT ALL FINAL GRADING AND STABILIZATION CAN TAKE PLACE AT ONE TIME.
- 33. COMPLETED SLOPES SHALL BE SEEDED AND MULCHED (OR BLANKETED, IF APPLICABLE) AS THE EXCAVATION PROCEEDS TO THE EXTENT CONSIDERED DESIRABLE AND PRACTICAL. PERMANENT SEEDING SHALL BE USED WHENEVER POSSIBLE. UNDER NO CIRCUMSTANCES SHALL THE CONTRACTOR PROLONG FINAL GRADING AND SHAPING SO THAT THE ENTIRE PROJECT CAN BE
- 34. THE SITE SHOULD BE PHASED IN A WAY THAT REDUCES THE AMOUNT OF STRIPPED. UNSTABILIZED AREAS WITHIN THE SITE AT ANY ONE TIME. MASS GRADING THE ENTIRE SITE SHOULD BE AVOIDED AS TO PREVENT EROSION ON SITE AND SEDIMENTATION
- 35. PRIOR TO RELEASE OF THE CREEK FLOW INTO THE NEWLY CREATED CHANNEL, THE CHANNEL BOTTOM AND BANKS MUST BE ADEQUATELY STABILIZED WITH VEGETATION OR A PRE-APPROVED ALTERNATIVE MEASURE TO WITHSTAND THE EROSIVE FORCES OF THE ORIGINAL CREEK FLOW. A MEETING WITH ALL PERTINENT PARTIES, INCLUDING THE KDSWCD, SHALL BE HELD PRIOR TO ANY CREEK RELEASES TO DETERMINE THE READINESS OF THE CREEK.
- 36. ONCE THE CONTRIBUTING AREA OF EACH SEDIMENTATION BASIN IS STABILIZED, THE BASIN NEEDS TO BE CLEANED OUT AND THE FINAL PROPOSED GRADE MUST BE ACHIEVED. 37. FOR INSTALLATION OF ALL FLARED END SECTIONS IN WETLAND OR RIPARIAN AREAS, WORK IN OR NEAR THE WETLAND MUST
- BE CONDUCTED IN LOW OR NO FLOW CONDITIONS. THE WORK AREA TEMPORARILY STABILIZED AT THE END OF EACH DAY, AND THE UPSTREAM RECEIVING AREA STABILIZED BEFORE THE PIPE IS PUT "ONLINE" TO THE WETLAND. 38. BARRIER PROTECTION SHALL BE PLACED AT THE LIMITS OF SOIL DISTURBANCE FOR ALL UNDISTURBED WETLAND, FLOODPLAIN,
- WATERS AND BUFFER AREAS, AND SHALL BE: • DUAL ROW OF SILT FENCE, AND A ROW OF ORANGE CONSTRUCTION FENCE; OR
- DUAL SILT FENCE BARRIER, WITH ONE OF THE FENCES BEING OF HIGH VISIBILITY MATERIAL.
- ALTERNATE PRACTICES OFFERING COMPARABLE PROTECTION TO WETLAND, FLOODPLAIN, WATERS, AND BUFFER MAY BE USED TO PREVENT IMPACT WHERE APPLICABLE.
- ADDITIONAL SOIL EROSION AND SEDIMENT CONTROLS MAY BE REQUIRED TO ADEQUATELY PROTECT THESE SITES.
- 39. ALL DROP INLETS ON AND ADJACENT TO THE SITE MUST HAVE A SEDIMENT TRAPPING OR CONTAINMENT DEVICE INSTALLED DURING CONSTRUCTION ACTIVITIES. FILTER FABRIC ON ITS OWN IS NOT AN APPROVED METHOD. A MANUFACTURE'S SPEC SHOULD BE USED FOR PREFABRICATED DROP INLET PROTECTION AND SHOULD BE AS RESTRICTIVE AS THE ILLINOIS URBAN MANUAL STANDARD 861 FOR INLET PROTECTION
- 40. ALL DEWATERING OPERATIONS SHALL FOLLOW ILLINOIS URBAN MANUAL PRACTICE STANDARD 813.

"I CERTIFY UNDER PENALTY OF LAW THAT I UNDERSTAND THE TERMS AND CONDITIONS OF THE GENERAL NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES) PERMIT (ILR10) THAT AUTHORIZES THE STORM WATER DISCHARGES ASSOCIATED WITH INDUSTRIAL ACTIVITY FROM THE CONSTRUCTION SITE IDENTIFIED AS PART OF THIS CERTIFICATION."

__ CONTRACTOR SIGNATURE

A*pproved by*: MN

DRAWN BY:

DESCRIPTION

PERMANENTLY SEEDED AT ONE TIME.

2416 GALEN DRIVE 10 S. RIVERSIDE PLAZA, SUITE 875 CHAMPAIGN, ILLINOIS 61821 PHONE (217) 351-6268 FAX (217) 355-1902

WEST BRANCH DUPAGE RIVER STABILIZATION

STORMWATER POLLUTION PREVENTION PLAN GENERAL NOTES AND DETAILS

SCALE: N.T.S. *DATE:* July, 2024 *JOB NO*: W23198 SHEET 14 OF

USACE Requirements for In-Stream Construction Activities

Work within a waterway must meet the following standards:

the coffered area to perform the required work.

Dewatering Bag Standard Drawing

within the effluent

SUCTION HOSE-

Installation and Use:

Maintenance and Disposal:

-MIL POLYETHYLENE -

Letters 6" Min. Height-

CONCRETÉ

WASHOUT

area

SIGN DETAIL

facility. OR; as directed by engineer or inspector

0000000

0000000

PLAN VIEW

6" WIRE STAPLE OR SANDBA

(ANCHOR EVERY 2' AT TOP OF SLOPE)

4"x4"x6' Wood Post or

Maintaining temporary concrete washout facilities shall include

Facility shall be cleaned or reconstructed in a new area once washout becomes two—thirds full.

removing and disposing of hardend concrete and/or slurry and returning the facilitities to a functional condition.

TEMPORARY CONCRETE

Work in the waterway should be timed to take place during low or no-flow conditions. Low flow conditions are flow at or below the normal water elevation. 2. The plan will be designed to allow for the conveyance of the 2-year peak flow past the work area without

overtopping the cofferdam. The Corps has the discretion to reduce this requirement if documented by the applicant to be infeasible or unnecessary. . Water shall be isolated from the in—stream work area using a cofferdam constructed of nonerodible materials

4. The cofferdam must be constructed from the upland area and no equipment may enter flowing water at any time. If the installation of the cofferdam cannot be completed from shore and access is needed to reach the area to be coffered, other measures, such as the construction of a causeway, will be necessary to ensure that equipment does not enter the water. Once the cofferdam is in place and the isolated area is dewatered, equipment may enter

(steel sheets, aqua barriers, rip rap and geotextile liner, etc.). Earthen cofferdams are not permissible.

is considered clean if it does not result in a visually identifiable degradation of water clarity.

The purpose of a Dewatering Bag is to collect sediment contained in the discharged water, to

prevent the scour and erosion from water exiting a pipe at high velocity, to defuse the water

over a wider area to minimize erosion as the water drains away, and to retain oil contained

WRAP ROPF-

Please Dewatering Bag on the ground or on a trailer over a relatively level, stabilized area.

2. Insert discharge pipe a minimum of 5 ft. inside dewatering bad and secure with a rope wrapped

3. Replace Dewatering Bag when half full of sediment or when the sediment has reduced the flow

Remove and dispose of accumulated sediment. Dispose of bag at an appropriate recycling or solid waste

A dewatering bag should be used anytime water is pumped on the site.

DISCHARGE -

6 times around the snout over a 6 inch width of the bag.

rate of the pump discharge to an impractical amount.

5. If bypass pumping is necessary, the intake hose shall be placed on a stable surface or floated to prevent sediment from entering the hose. The bypass discharge shall be placed on a nonerodible, energy dissipating surface prior to rejoining the stream flow and shall not cause erosion. Filtering of bypass water is not necessary unless the bypass water has become sediment-laden as a result of the current construction activities.


6. During dewatering of the coffered work area, all sediment-laden water must be filtered to remove sediment. Possible options for sediment removal include baffle systems, anionic polymers systems, dewatering bags, or other appropriate methods. Water shall have sediment removed prior to being re—introduced to the downstream waterway. A stabilized conveyance from the dewatering device to the waterway must be identified in the plan. Discharge water

7. The area from the toe to the top of the side slope shall be temporarily stabilized during construction to reduce the potential for erosion. All areas disturbed due to construction activities shall be restored to proposed conditions and fully stabilized prior to accepting flows.

DEWATERING


EARTHEN BERM ANCHOR SECTIONS

SUBGRADE ANCHOR SECTIONS





ALL WOOD MEMBERS


ARE 6"X6"



ROLLED EROSION CONTROL PRODUCTS







3/16" GALVANIZED

CONNECT LOOPS WITH

3/16" CABLE CLAMPS

INSTALL MATS ON TOP OF

THAT COVERS THE ENTIRE

CROSSING AREA.

TEMPORARY SOIL STOCKPILE DETAIL

NON-WOVEN GEOTEXTILE FABRIC

— Toe of Stockpile Slope

STANDARD DWG. NO


SHEET 1 OF 1


DATE JANUARY 2017

IUM-627

STEEL CABLE









CONSTRUCTION FENCE DETAIL

. FENCE POSTS SHALL BE EITHER STANDARD STEEL POSTS OR WOOD POSTS WITH A MINIMUM CROSS SECTIONAL AREA OF 3.0 SQ. IN. 2. THE FENCE MAY BE EITHER 40" HIGH SNOW FENCE, 40" PLASTIC WEB FENCING OR ANY OTHER MATERIAL AS APPROVED BY THE ENGINEER/INSPECTOR.





POST AND FENCE DETAIL

1. THE FENCE SHALL BE LOCATED A MINIMUM OF 1 FOOT OUTSIDE THE DRIP LINE OF THE TREE TO BE SAVED AND IN NO CASE CLOSER THAN 5 FEET TO THE TRUNK OF ANY TREE.

2. FENCE POSTS SHALL BE EITHER STANDARD STEEL POSTS OR WOOD POSTS WITH A MINUMUM CROSS SECTIONAL AREA OF 3.0 SQ. IN.

3. THE FENCE MAY BE EITHER 40" HIGH SNOW FENCE, 40" PLASTIC WEB FENCING OR ANY OTHER MATERIAL AS APPROVED BY THE PROJECT MANAGER

4. SURROND TRUNK WITH 2"X8"X8' BOARDS PER IDOT SECTION 201.06.b

TREE PROTECTION N.T.S.

DATE BY

AND ALL ATTACHMENTS WERE PREPARED UNDER MY DIRECTION TO ASSURE THAT QUALIFIED PERSONNEL PROPERLY GATHEREI AND EVALUATED THE INFORMATION SUBMITTED. BASED ON MY GATHERING THE INFORMATION. THE INFORMATION SUBMITTED IS SIGNIFICANT PENALTIES FOR SUBMITTING FALSE INFORMATION,


DESCRIPTION


3S701 WEST AVENUE, SUITE 150 WARRENVILLE, ILLINOIS 60555 PHONE (630) 393-3060


CHICAGO, ILLINOIS 60606 PHONE (312) 474-7841 FAX (312) 474-6099


NAPERVILLE PARK DISTRICT


Ground Surface —

















	Emergent Seed Mix	T
Botanical Name	Common Name	Lbs./Acre
Acorus americanus	Sweet Flag	0.31
Agrostis stolonifera	Bent Grass	1.250
Alisma subcordatum	Water Plantain	0.313
Ammannia robusta	Scarlet Loosestrife	0.039
Asclepias incarnata	Swamp Milkweed	0.11
Bidens cernua	Nodding Burmarigold	0.079
Boltonia asteroides	False Asterwort	0.156
Bulboschoenus fluviatilis	River Bulrush	0.156
Carex bebbii	Bebbs Sedge	1.250
Carex comosa	Bottlebrush Sedge	0.469
Carex hystericina	Porcupine Sedge	0.313
Carex lacustris	Common Lake Sedge	0.020
Carex lurida	Bottlebrush Sedge	0.31
Carex scoparia	Pointed Broom Sedge	1.250
Carex vulpinodea	Brown Fox Sedge	0.469
Cephalanthus occidentalis	Buttonbush	0.039
Eleocharis erythropoda	Redrooted Spikerush	0.039
Eleocharis obtusa	Blunt Spikerush	0.156
Eleocharis ovata	Blunt Spike Rush	0.039
Eleocharis palustris major	Marsh Spikerush	0.039
Elymus canadensis	Canada Rye	1.250
Elymus virginicus	Virginia Rye	1.250
Eupatorium maculatum	Spotted Joe-Pye Weed	0.039
Eupatorium perfoliatum	Thoroughwort	0.039
Glyceria striata	Fowl Manna Grass	0.313
Hibiscus laevis	Halberdleaf Rose Mallow	0.234
Iris virginica	Blue Flag	0.469
Juncus balticus littoralis	Lake Shore Rush	0.156
Juncus effusus	Soft Rush	0.156
Juncus torreyi	Torreys Rush	0.23
Leersia oryzoides	Rice Cut Grass	0.62
Lobelia cardinalis	Cardinal Flower	0.020
Lycopus americanus	Common Water Horehound	0.020
Mimulus ringens	Monkey Flower	0.078
Penthorum sedoides	Ditch Stonecrop	0.039
Pontederia cordata	Pickerel Weed	0.78
Sagittaria latifolia	Common Arrowhead	0.62
Schoenoplectus acutus	Hardstem Bulrush	0.19
Schoenoplectus pungens	Chairmakers Rush	0.313
Schoenoplectus tabernaemontar		0.469
Sparganium americanum	American Bur Reed	0.078
Spartina pectinata	Cord Grass	0.469
Symphyotrichum lanceolatum	Panicled Aster	0.156
Symphyotrichum puniceum	Swamp Aster	0.156
- Jpanie cani	TOTAL	

Common Oat

Wheat/Wheatgrass Hybrid, Regreen or eq.

Scientific Name

Avena sativa

Bouteloua curtipendula	Side Oats Gramma	1.500
Calamagrostis canadensis	Blue Joint Grass	0.25
Carex annectens xanthocarpa	Small Yellow Fox Sedge	0.12
Carex bebbii	Bebb's Sedge	0.12
Carex brevior	Shorter Sedge	0.12
Carex cristatella	Crested Sedge	0.12
Carex normalis	Normal Sedge	0.12
Carex scoparia	Pointed Broom Sedge	0.12
Carex vulpinoidea	Fox Sedge	0.12
Coreopsis tripteris	Tall Coreopsis	0.12
Dalea candida	White Prairie Clover	0.12
Dalea pururea	Purple Prairie Clover	0.25
Desmodium canadense	Showy Tick Trefoil	0.15
Echinacea pallida	Pale Purple Coneflower	0.37
Echinacea purpurea	Purple Coneflower	0.50
Elymus virginicus	Virginia Wild Rye	1.50
Eryngium yuccifolium	Rattlesnake Master	0.50
Eupatorium maculatum	Spotted Joe Pye Weed	0.25
Eupatorium perfoliatum	Thoroughwort	0.06
Glyceria striata	Fowl Manna Grass	0.25
Helenium autumnale	Sneezeweed	0.18
Heliopsis helianthoides	Early Sunflower	0.25
Iris virginica shrevei	Blue Flag	0.12
Juncus dudleyi	Dudley's Rush	0.03
Juncus torreyi	Torreys Rush	0.06
Leersia oryzoides	Rice Cut Crass	1.00
Liatris pycnostachya	Prairie Blazing Star	0.03
Liatris spicata	Marsh Blazing Star	0.03
Lobelia siphilitica	Great Blue Lobelia	0.03
Lycopus americanus	Water Horehound	0.06
Monarda fistulosa	Bergamont	0.25
Oligoneuron rigidum	Stiff Goldenrod	0.12
Panicum virgatum	Switch Grass	1.00
Physostegia virginiana	False Dragonhead	0.06
Pycnanthemum virginainum	Common Mountain Mint	0.16
Ratibida pinnata	Yellow Coneflower	0.25
Rudbeckia hirta	Black-Eyed Susan	0.25
Rudbeckia laciniata	Wild Golden Glow	0.06
Rudbeckia subtomentosa	Sweet Coneflower	0.25
Schizachyrium scoparium	Little Bluestem	1.50
Scirpus atrovirens	Dark Green Rush	0.12
Silphium integrifolium	Rosinweed	0.25
Silphium laciniatum	Compass Plant	0.12
Silphium perfoliatum	Cup Plant	0.25
Silphium terebinthinaceum	Prairie Dock	0.25
Spartina pectinata	Cord Grass	0.25
Symphyotrichum laeve	Smooth Blue Aster	0.12
Symphyotrichum novae-angliae		0.25
Symphyotrichum oolentangiens		0.12
Verbena hastata	Blue Vervain	0.25
Vernonia fasciculata	Common Ironweed	0.06
Varania a akuuna viirainia	Culveria Doot	0.06

Transitional Buffer Seed Mix					
Scientific Name	Common Name	Lbs./Acre			
Bouteloua curtipendula	Side-Oats gramma	15.000			
Buchloe dactyloides'BOWIE'	Bowie Buffalo Grass	2.000			
Carex annectens	Yellow-fruited Sedge	0.063			
Carex bicknellii	Bicknells Sedge	0.125			
Carex brevior	Shorter Sedge	0.12			
Carex molesta	Field Oval Sedge	0.125			
Carex vulpinoidea	Brown fox Sedge	0.125			
Elymus Canadensis	Canada Wild Rye	3.000			
Schizachyrium scoparium	Little Bluestem	20.000			
-	TOTAL	40.563			

River Plugs (14,000/ACRE)*			2024	2025	IOBE 202
Scientific Name	Common Name	Quantity%	Quantity	Quantity	Quantity
Acornus calamus	Sweet Flag	5.0%	100	50	
Carex aquatilis	Water Sedge	5.0%	100	50	
Carex lacustris	Common Lake Sedge	5.0%	100	50	
Carex trichocarpa	Hairy-Fruited Sedge	10.0%	150	50	5
Eleocharis palustris	Great Spike Rush	5.0%	100	50	
Hibiscus laevis	Halberd-Leaved Rose Mallow	7.0%	100	50	5
Iris virginica shrevei	Blue Flag	5.0%	100	50	
Juncus effusus	Common Rush	5.0%	100	50	
Justicia americana	Water Willow	5.0%	100	50	
Schoenoplectus acutus	Hardstem Bulrush	5.0%	100	50	
Schoenoplectus fluviatilis	River Bulrush	5.0%	100	50	
Schoenoplectus pungens	Chairmaker's Bulrush	8.0%	100	50	5
Schoenoplectus tabernaemontani	Softstem Bulrush	5.0%	100	50	
Scirpus atrovens	Dark Green Rush	5.0%	100	50	
Scirpus cyperinus	Wool Grass	5.0%	100	50	
Sparganium eurycarpum	Common Bur Reed	5.0%	100	50	
Spartina pectinata	Prairie Cord Grass	10.0%	150	50	5
	TOTAL PLUGS	100%	1800	850	20

Scientific Name	entific Name WI Common Name			
	•	TREES		
Betula nigra	(FACW)	River Birch	1.5" Caliper	
Carpinus caroliniana	(FAC)	Blue Beech	1.5" Caliper	
Carya cordiformis	(FACU)	Bitternut Hickory	1.5" Caliper	
Carya ovata	(FACU)	Shagbark Hickory	1.5" Caliper	
Cercis canadensis	(FACU)	Redbud	1.5" Caliper	
Crataegus mollis	(FACU-)	Downy Hawthorn	1.5" Caliper	
Gymnocladus dioica	(UPL)	Kentucky Coffee Tree	1.5" Caliper	;
Ostrya virginiana	(FACU-)	Ironwood	1.5" Caliper	,
Platanus occidentalis	(FACW)	Sycamore	1.5" Caliper	7
Quercus alba	(FAC)	White Oak	1.5" Caliper	,
Quercus bicolor	(FACW+)	Swamp White Oak	1.5" Caliper	;
Quercus macrocarpa	(FAC)	Bur Oak	1.5" Caliper	;
		TOTAL		30
		SHRUBS		
Amorpha fruiticosa	(FACW+)	Indigo Bush	5 gal	(
Cephalanthus occidentalis	(OBL)	Buttonbush	5 gal	!
Cornus obliqua	(FACW+)	Silky Dogwood	5 gal	(
Cornus stolonifera	(FACW+)	Red Osier Dogwood	5 gal	(
Corylus americana	(FACU-)	American Filbert	5 gal	(
Hamamelis virginiana	(FACU)	Common Witchhazel	5 gal	(
Lindera benzoin	(FACW-)	Spicebush	5 gal	(
Physocarpus opulifolius	(FACW-)	Ninebark	5 gal	,
Ribes americanum	(FACW-)	Wild Black Currant	5 gal	
Rosa palustris	(OBL)	Swamp Rose	5 gal	
Sambucus canadensis	(FACW)	Common Elderberry	5 gal	
Viburnum lentago	(FAC+)	Nannyberry	5 gal	
Viburnum prunifolium	(FACU)	Blackhaw	5 gal	
<u>.</u>	1 '	TOTAL	-	9

TREES AND SHRUBS

ALL TREES AND SHRUBS SHALL BE FIELD LOCATED UPON DELIVERY. AN AS-BUILT OF PLANTED LOCATIONS ALONG THE BANK AND WITHIN THE FLOODPLAIN ADJACENT TO THE PATH WILL BE PROVIDED.

<u>LEGEND</u>

TRANSITIONAL BUFFER SEED MIX, 0.18 ACRES



SHALLOW EMERGENT SEED MIX & RIVER PLUGS, 0.10 ACRES

%%%%%%%% OPEN RIPARIAN SEED MIX, 0.85 ACRES



STREAM BARB



RIVER PLUGS, 765 L.F.

ALL DISTURBED AREAS SHALL BE SEEDED AND BLANKETED WITH TEMPORARY COVER CROP, SPECIFIED SEED AND EROSION CONTROL BLANKET.

SEE SPECIFICATIONS FOR SEED AND PLUG MIXES.

REVISIONS:							
DATE	BY	DESCRIPTION	DATE	BY	DESCRIPTION	DRAWN BY:	RT
						CHECKED BY:	EP
						APPROVED BY	r: MM

Lbs./Acre 32.000



Culver's Root

Golden Alexander

Veronicastrum virginicum

Zizia aurea

0.063

0.063


TOTAL 16.626

CHAMPAIGN, ILLINOIS 61821 PHONE (217) 351-6268 FAX (217) 355-1902


WEST BRANCH DuPAGE RIVER STABILIZATION NAPERVILLE PARK DISTRICT

PLANTING PLAN STA. 110+50 TO STA. 116+13


SCALE: 1"=20' *DATE*: July, 2024 *JOB NO*: W23198 SHEET_ 18_OF__




SHRUB DETAIL



WILDLIFE TREE PROTECTION DETAIL (SECTION)
NOT TO SCALE




TYPICAL PLANTING CROSS SECTION




WILDLIFE TREE PROTECTION DETAIL

(PLAN VIEW)
NOT TO SCALE



NOTE:
1. PROVIDE GOOSE GRID OVER ALL PLUGGED AREAS.

GOOSE GRID BARRIER DETAIL



DECIDUOUS TREE PLANTING
NOT TO SCALE

REVISIONS: DRAWN BY: DATE BY DESCRIPTION DESCRIPTION DATE BY APPROVED BY: MM



CHAMPAIGN, ILLINOIS 61821 PHONE (217) 351-6268 FAX (217) 355-1902


WEST BRANCH DuPAGE RIVER STABILIZATION NAPERVILLE PARK DISTRICT

PLANTING DETAILS

 SCALE:
 N.T.S.


 DATE:
 July, 2024


 JOB NO:
 W23198
 SHEET_19_0F__



- 1. ROCK SLOPE SHALL BE CONSTRUCTED ON STABLE BASE
- 2. ROCK SHALL BE 3"-9" DIAMETER COBBLE.
- 3. ROCK SHALL BE INSTALLED IN AN OSCULATING PATTERN TO
- 4. RIVER PLUG PLANTINGS IN ROCK 6" BELOW AND UP TO NORMAL WATER LEVEL.
- 5. INSTALL SC150BN OR EQUIVALENT ALONG DISTURBED AREAS FROM THE TOE OF SLOPE TO TOP OF BANK.
- 6. INSTALL S75BN OR EQUIVALENT ALONG DISTURBED AREAS BEYOND TOP OF BANK.


VEGETATED ROCK TOE






FILTER FABRIC AS SOIL SEPERATOR, WRAP TOP — OF GRAVEL TO PREVENT GRAVEL WASHOUT

> SECTION A - A



STONE OUTCROPPING DETAIL

 $\mathsf{B}\mathsf{-}\mathsf{B}$



REVISIONS:							
DATE	BY	DESCRIPTION	DATE	BY	DESCRIPTION	DRAWN BY:	RT
						1	
						CHECKED BY:	EF
						APPROVED BY:	MM



CHAMPAIGN, ILLINOIS 61821 PHONE (217) 351-6268 FAX (217) 355-1902

WEST BRANCH DUPAGE RIVER STABILIZATION NAPERVILLE PARK DISTRICT

BANK STABILIZATION DETAILS

DATE: July, 2024 *JOB NO:* W23198 SHEET 20 OF .