

MATERIAL QUOTE

QUICK SERVICE QUOTATION

This quotation constitutes an offer to sell which offer expressly limits acceptance to the terms of this offer on the back of this quotation. This offer shall be firm for a period of thirty (30) business days from the date of this offer. Subject to Buyers credit worthiness, the return of this form with a Purchase Order number or any other reasonable manner of acceptance will be sufficient to form an agreement on the terms and conditions on the back of this quotation.



WESCO
DISTRIBUTIONSM

WESCO Distribution

2401 International
Woodridge, IL 60517
Phone: 630-327-7017
Fax: 630-633-2026

DATE:	2/16/23	TO:	CITY OF NAPERVILLE
PROJECT NAME:	JEFFERSON BATTERY SYSTEM		
QUOTE#	SOURCEWELL CONTRACT 091422WES	ATTENTION:	EMILY CRAIG
SALESPERSON:	MATT BOGGS		

Item	Qty	DESCRIPTION	UNIT PRICE	U/M	TOTAL
BATT	1	C&D Technologies 3DJ-11 HP 125 Volt String (20 Jars/ 60 Cells), vented lead calcium battery. 235 A-hr. at the 8 hr. rate to 1.75 VPC at 77°F, 1.215 specific gravity Three cell monoblocs PVC monobloc containers - (Flame Retardant) 20 + year design life, Rectangular lead terminal posts Includes: - I.E.E.E. Std 450 Capacity Acceptance Test - Full Accessory Kit includes terminal plates Warranty: 20 year limited, (3) year full (17) years prorated	\$32,707.00	L	\$32,707.00
RACK	1	-Rack-ST2231(SGR2) - ST2231 1-tier, 2- step rack Rack Dimensions: Length = 88.58 inch Width = 33.86 inch - SGR 2 = 29.92 inch Height= 11.22 inch	\$1,076.00	E	\$1,076.00
SPILL	1	Spill Containment System. Includes installation hardware and neutralization pillows	\$2,134.00	L	\$2,134.00
INSTALL	1	Installation of new rack, battery, and spill containment. Temporary battery bank during installation. Haul away and proper disposal of existing battery and rack.	\$9,147.00	L	\$9,147.00
COMM	1	Commissioning and testing of battery after installation, including delivery of test report within (1) week of installation. *EEPS recommends a return visit 60 days after installation	\$1,830.00	E	\$1,830.00

