



**ROOT BARRIERS**

THE CONTRACTOR SHALL INSTALL ROOT BARRIERS NEAR ALL NEWLY PLANTED TREES THAT ARE LOCATED WITHIN FIVE (5) FEET OF PAVING OR CURBS. ROOT BARRIERS SHALL BE "CENTURY" OR "DEE-ROOT" 24" DEEP PANELS (OR EQUAL). BARRIERS SHALL BE LOCATED IMMEDIATELY ADJACENT TO HARDSCAPE. INSTALL PANELS PER MANUFACTURER'S RECOMMENDATIONS. UNDER NO CIRCUMSTANCES SHALL THE CONTRACTOR USE ROOT BARRIERS OF A TYPE THAT COMPLETELY ENCLOSE THE ROOTBALL.

**MULCHES**

AFTER ALL PLANTING IS COMPLETE, CONTRACTOR SHALL INSTALL 3" THICK LAYER OF 1/2" SHREDDED WOOD MULCH IN ALL PLANTING AREAS (EXCEPT FOR TURF AND SEEDED AREAS). CONTRACTOR SHALL SUBMIT SAMPLES OF ALL MULCHES TO LANDSCAPE ARCHITECT AND OWNER FOR APPROVAL PRIOR TO CONSTRUCTION. ABSOLUTELY NO EXPOSED GROUND SHALL BE LEFT SHOWING ANYWHERE ON THE PROJECT AFTER MULCH HAS BEEN INSTALLED.

**COMPLIANCE**

ALL LANDSCAPING COMPLIES WITH THE SEPARATION DISTANCES FROM UTILITIES, AS SPECIFIED IN SECTION 5-10-3-10 (LANDSCAPING, SCREENING, AND TREE PRESERVATION- INSTALLATION).

**PLANTING LEGEND**

SYMBOL	BOTANIC NAME	COMMON NAME	SIZE	SPACING	QUANTITY	REMARKS
<b>TREES</b>						
BENI	Betula nigra	River Birch	2.5' cal., 10'-12" H	Per plan	11	
CECA	Conocarpus canaliculatus 'Appalachian Reef'	Appalachian Reef Redbud	2.5' cal., 10'-12" H	Per plan	8	
GIBI	Ginkgo biloba 'Princeton Sentry'	Princeton Sentry Ginkgo	2.5' cal., 10'-12" H	Per plan	5	male variety
<b>SHRUBS</b>						
ILGL	Ilex glabra 'Shamrock'	Shamrock Inkberry	#5 cont.	3' o.c.	59	
JUBC	Juniperus horizontalis 'Blue Chip'	Blue Chip Juniper	#5 cont.	5' o.c.	36	
PHCP	Physocarpus opulifolius 'SMPTW'	Tiny Wine Ninebark	#5 cont.	4' o.c.	19	
THOC	Thuja occidentalis 'Teichry'	Teichry Arborvitae	4 B&B	Per plan	12	
VILA	Viburnum lantana 'Mojican'	Mojican Wayfaringtree	4 B&B	Per plan	10	
<b>PERENNIALS AND ORNAMENTAL GRASSES</b>						
CAVC	Calamagrostis acutiflora 'Karl Foerster'	Karl Foerster Reed Grass	#3 cont.	24" o.c.	52	
HESC	Heuchera 'Southern Comfort'	Southern Comfort Coral Bells	#1 cont.	18" o.c.	18	sub: H. 'Caramel'
PEOR	Pennisetum orientale 'Karley Rose'	Karley Rose Fountain Grass	#1 cont.	18" o.c.	48	
<b>TURF</b>						
	Poa pratensis	Kentucky Bluegrass	Sod	---	---	

**LANDSCAPE CALCULATIONS**

<b>PARKWAY TREES</b>	
FRONTAGE LENGTH - ANNA MARIE LANE:	181 LF
TREES REQUIRED:	5 TREES (1 TREE PER 40 LF)
TREES PROVIDED:	5 TREES
FRONTAGE LENGTH - 95TH STREET:	181 LF
TREES REQUIRED:	5 TREES (1 TREE PER 40 LF)
TREES PROVIDED:	5 TREES
<b>PERIMETER LANDSCAPE</b>	
PROPERTY LINE LENGTH (WEST):	223 LF
TREES REQUIRED:	7 TREES (1 TREE PER 35 LF)
TREES PROVIDED:	7 TREES
PROPERTY LINE LENGTH (EAST):	223 LF
TREES REQUIRED:	3 TREES (1 TREE PER 70 LF)
TREES PROVIDED:	3 TREES

**GENERAL PLANTING NOTES**

- THE GENERAL CONTRACTOR IS RESPONSIBLE FOR REMOVING ALL EXISTING VEGETATION (EXCEPT WHERE NOTED TO REMAIN). BEFORE STARTING WORK, THE LANDSCAPE CONTRACTOR SHALL VERIFY THAT THE GRADE OF ALL LANDSCAPE AREAS IS WITHIN +/- 1" OF FINISH GRADE. THE LANDSCAPE CONTRACTOR SHALL NOTIFY THE OWNER IMMEDIATELY SHOULD ANY DISCREPANCIES EXIST. SEE SPECIFICATIONS FOR MORE DETAILED INSTRUCTION ON TURF AREA AND PLANTING BED PREPARATION.
- CONSTRUCT AND MAINTAIN FINISH GRADES IN LANDSCAPE AREAS AS SHOWN ON GRADING PLANS, AND CONSTRUCT AND MAINTAIN SLOPES AS RECOMMENDED BY THE GEOTECHNICAL REPORT. ALL LANDSCAPE AREAS SHALL HAVE POSITIVE DRAINAGE AWAY FROM STRUCTURES AT THE MINIMUM SLOPE SPECIFIED IN THE REPORT, AND AREAS OF POTENTIAL PONDING SHALL BE REGRADED TO BLEND IN WITH THE SURROUNDING GRADES AND ELIMINATE PONDING POTENTIAL. SHOULD ANY CONFLICTS AND/OR DISCREPANCIES ARISE BETWEEN THE GRADING PLANS, GEOTECHNICAL REPORT, THESE NOTES, AND ACTUAL CONDITIONS, THE CONTRACTOR SHALL IMMEDIATELY BRING SUCH ITEMS TO THE ATTENTION OF THE LANDSCAPE ARCHITECT, GENERAL CONTRACTOR, AND OWNER.
- ENSURE THAT THE GRADE IN SHRUB AREAS SHALL BE 2" BELOW FINISH GRADE AFTER INSTALLING SOIL AMENDMENTS, AND 1" BELOW FINISH GRADE IN SOO AREAS AFTER INSTALLING SOIL AMENDMENTS. MULCH COVER WITHIN 6" OF CONCRETE WALKS AND CURBS SHALL NOT PROTRUDE ABOVE THE FINISH SURFACE OF THE WALKS AND CURBS. MULCH COVER WITHIN 12" OF WALLS SHALL BE AT LEAST 3" LOWER THAN THE TOP OF WALL.
- INSTALL MULCH TOPDRESSING, TYPE AND DEPTH PER MULCH NOTE. IN ALL PLANTING BEDS AND TREE RINGS, DO NOT INSTALL MULCH WITHIN 6" OF TREE ROOT FLARE.
- INSTALL 1/2" GREEN STEEL EDGING BETWEEN ALL PLANTING BEDS AND TURF AREAS, AND BETWEEN GROUNDCOVERS AND OTHER PLANTS (WHERE INDICATED ON THE PLAN).
- HYDROMULCH ALL DISTURBED AREAS OUTSIDE OF PROPERTY LIMITS (UNLESS SHOWN AS SOO).
- ALL PLANT LOCATIONS ARE DIAGRAMMATIC. ACTUAL LOCATIONS SHALL BE VERIFIED WITH THE LANDSCAPE ARCHITECT OR DESIGNER PRIOR TO PLANTING. THE LANDSCAPE CONTRACTOR SHALL ENSURE THAT ALL REQUIREMENTS OF THE PERMITTING AUTHORITY ARE MET (I.E., MINIMUM PLANT QUANTITIES, PLANTING METHODS, TREE PROTECTION METHODS, ETC.).
- THE LANDSCAPE CONTRACTOR IS RESPONSIBLE FOR DETERMINING PLANT QUANTITIES. PLANT QUANTITIES SHOWN ON LEGENDS AND CALLOUTS ARE FOR GENERAL INFORMATION ONLY. IN THE EVENT OF A DISCREPANCY BETWEEN THE PLAN AND THE PLANT LEGEND, THE PLANT QUANTITY AS SHOWN ON THE PLAN FOR INDIVIDUAL SYMBOLS OR CALLOUT (FOR GROUNDCOVER PATTERNS) SHALL TAKE PRECEDENCE.
- NO SUBSTITUTIONS OF PLANT MATERIALS SHALL BE ALLOWED WITHOUT THE WRITTEN PERMISSION OF THE LANDSCAPE ARCHITECT.** IF SOME OF THE PLANTS ARE NOT AVAILABLE, THE LANDSCAPE CONTRACTOR SHALL NOTIFY THE LANDSCAPE ARCHITECT IN WRITING (FOR PROPER CHANNELS).
- PLANTS MAY BE INSPECTED AND APPROVED OR REJECTED ON THE JOBSITE BY THE OWNER OR OWNER'S REPRESENTATIVE.
- THE LANDSCAPE CONTRACTOR SHALL BE RESPONSIBLE FOR THE MAINTENANCE OF ALL WORK SHOWN ON THESE PLANS FOR 90 DAYS BEYOND FINAL ACCEPTANCE OF ALL LANDSCAPE WORK BY THE OWNER. LANDSCAPE MAINTENANCE SHALL INCLUDE WEEKLY SITE VISITS FOR THE FOLLOWING ACTIONS (AS APPROPRIATE): PROPER PRUNING, RESTAKING OF TREES, RESETTling OF PLANTS THAT HAVE SETTLED, MOVING AND AERATION OF LAWNS, WEEDING, RESEEDING AREAS WHICH HAVE NOT GERMINATED WELL, TREATING FOR INSECTS AND DISEASES, REPLACEMENT OF MULCH, REMOVAL OF LITTER, REPAIRS TO THE IRRIGATION SYSTEM DUE TO FAULTY PARTS AND/OR WORKMANSHIP, AND THE APPROPRIATE WATERING OF ALL PLANTINGS. THE LANDSCAPE CONTRACTOR SHALL MAINTAIN THE IRRIGATION SYSTEM IN PROPER WORKING ORDER, WITH SCHEDULING ADJUSTMENTS BY SEASON TO MAXIMIZE WATER CONSERVATION.
- SHOULD SEEDED AND/OR SOODED AREAS NOT BE COVERED BY AN AUTOMATIC IRRIGATION SYSTEM, THE LANDSCAPE CONTRACTOR SHALL BE RESPONSIBLE FOR WATERING THESE AREAS AND OBTAINING A FULL STAND OF GRASS AT NO ADDITIONAL COST TO THE OWNER.
- TO ACHIEVE FINAL ACCEPTANCE AT THE END OF THE MAINTENANCE PERIOD, ALL OF THE FOLLOWING CONDITIONS MUST OCCUR:
  - THE LANDSCAPE SHALL SHOW ACTIVE, HEALTHY GROWTH (WITH EXCEPTIONS MADE FOR SEASONAL DORMANCY). ALL PLANTS NOT MEETING THIS CONDITION SHALL BE REJECTED AND REPLACED BY HEALTHY PLANT MATERIAL PRIOR TO FINAL ACCEPTANCE.
  - ALL HARDSCAPE SHALL BE CLEANED PRIOR TO FINAL ACCEPTANCE.
  - SOODED AREAS MUST BE ACTIVELY GROWING AND MUST REACH A MINIMUM HEIGHT OF 1 1/2 INCHES BEFORE FIRST MOWING. HYDROMULCHED AREAS SHALL SHOW ACTIVE, HEALTHY GROWTH. BARE AREAS LARGER THAN TWELVE SQUARE INCHES MUST BE RESEODED OR RESEEDED (AS APPROPRIATE) PRIOR TO FINAL ACCEPTANCE. ALL SOODED TURF SHALL BE NEATLY MOWED.
- SEE SPECIFICATIONS AND DETAILS FOR FURTHER REQUIREMENTS.

PREPARED FOR: **CHRISTIAN BROTHERS AUTOMOTIVE CORP.**  
 333 PERDUE ROAD SUITE 200 DALLAS, TX 75243  
 972.933.8877 • 800.833.9444 • www.christianbrothers.com  
 (Landscape Architect Registration No. 20000000000000000000)

**Bollinger, Lach & Associates, Inc.**  
 17758 KATY FREEWAY, STE. 200  
 HOUSTON, TEXAS 77054  
 PH: (281) 975-8105

**CHRISTIAN BROTHERS AUTOMOTIVE CORP.**  
 CITY OF NAPERVILLE

SHEET NUMBER **LP-1**  
 10 OF 14

**EXHIBIT F**

